

Class Code	Material Class	Material	Description	Qty	Units	Brd Ft	Board Footage
*** Floor 1 - 1463-Main Floor ***							
===== 1st Floor Rough Carpentry =====							

PLATES:							
20	2 x Dimen Lumber	Plate Wall (P-Treat) 2x4	2"x 4"x RL' - #2&Btr PT-S4S (??)	395	lin ft	0.67	264.65
20	2 x Dimen Lumber	Plate Wall (P-Treat) 2x6	2"x 6"x RL' - #2&Btr PT-S4S (??)	49	lin ft	1.00	49.00
20	2 x Dimen Lumber	Plate Wall - (Top) 2x4	2"x 4"x RL' - Std&Btr S4S (??)	931	lin ft	0.67	623.77
20	2 x Dimen Lumber	Plate Wall - (Top) 2x6	2"x 6"x RL' - #2&Btr S4S (??)	101	lin ft	1.00	101.00
SubTotal:							1038.42
STUDS							
20	2 x Dimen Lumber	Stud 2x4 PreCut -104 1/4"	2"x 4"x 104 1/4" - Stud S4S (??)	519	each	6.00	3114.00
20	2 x Dimen Lumber	Stud 2x6 Precut -104 1/4"	2"x 6"x 104 1/4" - Stud S4S (??)	33	each	9.00	297.00
20	2 x Dimen Lumber	Wall Stud - 2"x 4"x 8'	2"x 4"x 8' - Std&Btr S4S (??)	13	each	5.33	69.29
20	2 x Dimen Lumber	Wall Stud- 2"x 4"x 8'	2"x 4"x 8' - Std&Btr S4S (??)	35	each	5.33	186.55
20	2 x Dimen Lumber	Wall Stud- 2"x 6"x 8'	2"x 6"x 8' - #2&Btr S4S (??)	14	each	8.00	112.00
20	2 x Dimen Lumber	Wall Stud - 2"x 4"x 10'	2"x 4"x 10' - Std&Btr S4S (??)	1	each	6.67	6.67
SubTotal:							3785.51
BRACE-BLOCK-BACKING							
20	2 x Dimen Lumber	Brace-Block-Backing-2x4	2"x 4"x RL' - Std&Btr S4S (??)	641	lin ft	0.67	429.47
20	2 x Dimen Lumber	Brace-Block-Backing-2x6	2"x 6"x RL' - #2&Btr S4S (??)	99	lin ft	1.00	99.00
20	2 x Dimen Lumber	Ledger - Wall 2"x4"	2"x 4"x RL' - Std&Btr S4S (??)	14	lin ft	0.67	9.38
20	2 x Dimen Lumber	Brace (TEMP) 2x4x16'	2"x 4"x 16' - Std&Btr S4S (??)	26	each	10.67	277.42
SubTotal:							815.27
POSTS							
30	3 x Dimen Lumber	Stud 3x4 Precut -104 1/4"	3"x 4"x 104 1/4" - Stud S4S (??)	4	each	9.00	36.00
40	4 x Dimen Lumber	Stud 4x4 Precut -104 1/4"	4"x 4"x 104 1/4" - Stud S4S (??)	2	each	12.00	24.00
40	4 x Dimen Lumber	Stud 4x6 Precut-104 1/4"	4"x 6"x 104 1/4" - Stud S4S (??)	2	each	18.00	36.00
SubTotal:							96.00
SHEATHING							
500	Sheathing	Sheath Wall-(OSB)- 9'0"	3/8"x 4'x 9' - OSB Sheathing	17	shts	36.00	612.00
500	Sheathing	Platform-Mech. Sheathing	23/32"x 4'x 8' - OSB Sheathing	2	shts	32.00	64.00
500	Sheathing	Ext. Pot Shelf - 3/8"	3/8"x 4'x 8' - OSB Sheathing	1	shts	32.00	32.00
SubTotal:							708.00
HEADER							
40	4 x Dimen Lumber	Header-(Dimen)- 4x6	4"x 6"x RL' - #2&Btr S4S (??)	114	lin ft	2.00	228.00
40	4 x Dimen Lumber	Header-(Dimen)- 4x8	4"x 8"x RL' - #2&Btr S4S (??)	8	lin ft	2.67	21.36
40	4 x Dimen Lumber	Header-(Dimen)- 4x10	4"x 10"x RL' - #2&Btr S4S (??)	12	lin ft	3.33	39.96
21	Eng Lumber	Header-(LVL1.9e)-14"	1 3/4"x 14"x RL' (LVL 1.9e)	33	lin ft	2.33	76.89
SubTotal:							366.21
BEAM							
40	4 x Dimen Lumber	Beam-(Dimen)- 4x6	4"x 6"x RL' - #2&Btr S4S (??)	14	lin ft	2.00	28.00
40	4 x Dimen Lumber	Beam-(Dimen)- 4x8	4"x 8"x RL' - #2&Btr S4S (??)	7	lin ft	2.67	18.69
SubTotal:							46.69
MISC ROUGH CARPENTRY							
999	1 x Dimen Lumber	Stucco Mold - 18'0'	13/16"x 1-1/2"x 8' RWD Stucco Moulk	1	each	1.33	1.33
999	1 x Dimen Lumber	Stucco Mold - 16'0"	13/16"x 1-1/2"x 16' RWD Stucco Mou	1	each	2.67	2.67
20	2 x Dimen Lumber	Door Buck - 2"x6"x18' RS	2"x 6"x 18' - Sel/Com SS1S2e (??)	1	each	18.00	18.00
20	2 x Dimen Lumber	Door Buck - 2"x6"x8' RS	2"x 6"x 8' - Sel/Com SS1S2e (??)	2	each	8.00	16.00
SubTotal:							38.00
*** Floor 2 - made up 2nd floor ***							

Class Code	Material Class	Material	Description	Qty	Units	Brd Ft	Board Footage
===== 2nd Floor Rough Carpentry =====							

PLATES							
20	2 x Dimen Lumber	Plate Wall (P-Treat) 2x4	2"x 4"x RL' - #2&Btr PT-S4S (??)	355	lin ft	0.67	237.85
20	2 x Dimen Lumber	Plate Wall (P-Treat) 2x6	2"x 6"x RL' - #2&Btr PT-S4S (??)	38	lin ft	1.00	38.00
20	2 x Dimen Lumber	Plate Wall - (Top) 2x4	2"x 4"x RL' - Std&Btr S4S (??)	765	lin ft	0.67	512.55
20	2 x Dimen Lumber	Plate Wall - (Top) 2x6	2"x 6"x RL' - #2&Btr S4S (??)	79	lin ft	1.00	79.00
SubTotal:							867.40
STUDS							
20	2 x Dimen Lumber	Stud 2x4 Precut - 92 1/4"	2"x 4"x 92 1/4" - Stud S4S (??)	443	each	5.33	2361.19
20	2 x Dimen Lumber	Stud 2x6 Precut - 92 1/4"	2"x 6"x 92 1/4" - Stud S4S (??)	41	each	8.00	328.00
20	2 x Dimen Lumber	Wall Stud- 2"x 4"x 8'	2"x 4"x 8' - Std&Btr S4S (??)	17	each	5.33	90.61
20	2 x Dimen Lumber	Wall Stud- 2"x 6"x 8'	2"x 6"x 8' - #2&Btr S4S (??)	2	each	8.00	16.00
SubTotal:							2795.80
BRACE-BLOCK-BACKING							
20	2 x Dimen Lumber	Brace-Block-Backing-2x4	2"x 4"x RL' - Std&Btr S4S (??)	517	lin ft	0.67	346.39
20	2 x Dimen Lumber	Brace-Block-Backing-2x6	2"x 6"x RL' - #2&Btr S4S (??)	51	lin ft	1.00	51.00
20	2 x Dimen Lumber	Ledger - Wall 2"x4"	2"x 4"x RL' - Std&Btr S4S (??)	10	lin ft	0.67	6.70
20	2 x Dimen Lumber	Brace (TEMP) 2x4x16'	2"x 4"x 16' - Std&Btr S4S (??)	25	each	10.67	266.75
SubTotal:							670.84
SHEATHING							
500	Sheathing	Sheath Wall-(OSB)- 9'0"	3/8"x 4x 9' - OSB Sheathing	16	shts	36.00	576.00
500	Sheathing	Platform-Mech. Sheathing	23/32"x 4x 8' - OSB Sheathing	2	shts	32.00	64.00
500	Sheathing	Ext. Pot Shelf - 3/8"	3/8"x 4x 8' - OSB Sheathing	1	shts	32.00	32.00
SubTotal:							672.00
HEADER							
20	2 x Dimen Lumber	Header-(Dimen)- 2x4	2"x 4"x RL' - Std&Btr S4S (??)	32	lin ft	0.67	21.44
40	4 x Dimen Lumber	Header-(Dimen)- 4x6	4"x 6"x RL' - #2&Btr S4S (??)	102	lin ft	2.00	204.00
40	4 x Dimen Lumber	Header-(Dimen)- 4x8	4"x 8"x RL' - #2&Btr S4S (??)	8	lin ft	2.67	21.36
40	4 x Dimen Lumber	Header-(Dimen)- 4x10	4"x 10"x RL' - #2&Btr S4S (??)	12	lin ft	3.33	39.96
SubTotal:							286.76
BEAM							
40	4 x Dimen Lumber	Beam-(Dimen)- 4x8	4"x 8"x RL' - #2&Btr S4S (??)	7	lin ft	2.67	18.69
SubTotal:							18.69
*** All Floors ***							
===== ROOF / ELEVATION PACK =====							

BRACE-BLOCK-BACKING							
20	2 x Dimen Lumber	Brace-Roof Truss 2x4x12'	2"x 4"x 12' - Std&Btr S4S (??)	27	each	8.00	216.00
10	1 x Dimen Lumber	Brace-Roof Truss 1x6xRL'	1"x 6"x RL' - #2&Btr S4S (??)	169	lin ft	0.50	84.50
SubTotal:							300.50
TRUSSES & RAFTERS							
20	2 x Dimen Lumber	Rafter (2x6)	2"x 6"x RL' - #2&Btr S4S (??)	421	lin ft	1.00	421.00
SubTotal:							421.00
SHEATHING							
500	Sheathing	Sheath-Roof 15/32" (OSB)	15/32"x 4x 8' - OSB Sheathing	85	shts	36.00	3060.00
SubTotal:							3060.00
Total for all Floors:							15987.09